

[illegible]

[illegible]

[illegible]

[illegible]

BILL N°5 FIRE PROTECTION SYSTEM				Page:	5 of 7
Section 1. HAND HELD FIRE PROTECTION EQUIPMENT (FIRE HYDRANTS, FIRE HOSE REELS & PIPING)					
Refer to drawings: 21B09-F-501-04, 21B09-F-501-05 & 21B09-F-501-06					
Item N°	Description	Unit	Qty.	Rate	Amount R
1	EXISTING HOSE REEL SERVICING Servicing of fire hose reel	No.	5		
2	HOSE REEL AND EXTINGUISHER INSTALLATION Supply, delivery, installation, connection, testing and commissioning of a completely functioning hose reel installation as itemised below:				
2.1	Supply & Install Fire Hose Reels (30m long) , complete with chromium plated 25mm valve fittings (not plastic), with pressure gauges, hose roller guides and service stickers (on the drum and face of the hose reel) with all required fixings.	No.	1		
3	HOSE REEL PIPING SUPPLY & INSTALLATION Supply, delivery, installation, connection, testing and commissioning of a completely functioning hose reel installation as itemised below:				
3.1	Supply & Install of Black Steel c/w fittings and supports for above ground installation as specified				
3.1.1	25mm Nominal Bore	m	20		
3.1.2	Painting and identification of all fire pipe work as per SABS	Item	1		
3.1.3	Pipework Flushing as per SABS	Item	1		
3.1.4	Pipework Pressure Test as per SABS	Item	1		
4	Any other items (specify)	Item	Sum		
Total for Bill No.5 carried forward to the final collection page:					

Total for bill No.4 carried forward to the final collection page:

