

[illegible]

[illegible]

BILL N°3 FIRE PROTECTION SYSTEM				Page:	3 of 7
Section 1. HAND HELD FIRE PROTECTION EQUIPMENT (FIRE EXTINGUISHERS) Refer to drawings: 21B09-F-504-05					
Item N°	Description	Unit	Qty.	Rate	Amount R c
1	FIRE EXTINGUISHERS INSTALLATION: Supply, delivery, installation, connection, testing and commissioning of a completely functioning Fire extinguishers installation as itemised below:				
1.1	4,5 kg DCP Fire Extinguisher	No.	7		
2	STATUTORY EMERGENCY SIGNAGE: Supply, delivery, installation, cleaning and commissioning of statutory emergency signage installation in accordance with this document and SANS 1186 Parts 1 and 5 – including all anodised aluminium frames, hooks, chains and other fixing materials as required. Note all signage must 190mm high, Photoluminescent, with a visible SABS stamp of approval, and must be mechanically screw fixed.				
2.1	Running man & arrow sign - E1	No.	7		
2.2	Running man & arrow sign - E2	No.	6		
2.3	Running man, arrow pointing down - E3	No.	5		
2.4	Arrow and extinguisher sign - F13	No.	2		
2.5	Arrow and extinguisher sign - F19	No.	1		
2.6	Arrow, extinguisher, hose reel sign - F4	No.	2		
2.7	Arrow, extinguisher, hose reel sign - F5	No.	5		
2.8	Arrow, extinguisher, hose reel sign - F6	No.	5		
2.9	Running man, stair & arrow sign - E17	No.	1		
2.10	Break Glass unit - F31	No.	3		
2.11	Fire exit keep clear - F45	No.	1		
2.12	Exit sign - E6	No.	1		
3	FIRE RATED DOORS: Supply, delivery, of Fire doors equal and approved to Allandale, Amador, & SDA. The doors must be SABS approved, with certification tags on both the door frame and door leaf as itemised below: Note the fire doors must have steel frames with 25mm rebates as per SANS 10400 and SANS 1253				
3.1	60 minute fire rated doors - 811mm (wide) x 2100mm (high), Single door, single swing complete with door closer.	No.	1		
4	FIRE SEALING: Supply, and Installation of SABS approved 60 minute Fire sealing elements with certification reports as itemised below:				
4.1	Supply and install 60min fire rated fire sealing elements to gap between top of separation wall (between fire zones & Underside of slab/roof).	m	23		
4.2	Supply and install fire sealing for Shaft floor penetration & wall - fire water pipe, electrical cables, data cables, etc	Item	2		
5	Any other items (Specify)	Item	Sum		
Total for Bill No.3 carried forward to the final collection page:					

[illegible]



Total for bill No.4 carried forward to the final collection page:

