

ALL PLANS AND DOCUMENTS ARE THE SOLE PROPERTY OF SARS FACILITIES SPACE PLANNING. NO REPRODUCTION MAY BE MADE WITHOUT THE WRITTEN CONSENT OF SARS FACILITIES. **NOTE:** ALL DIMENSIONS MUST BE VERIFIED ON SITE BEFORE THE COMMENCEMENT OF WORK

DATE	NO	AMENDMENT
------	----	-----------

AMENDMENT SCHEDULE

--	--	--

APPROVALS

Standards:

Client:

IT:

Security:

Health & Safety:

Maintenance:

DATE 10/2023

SCALE 1:100 (A1)

DRAWN BY GM


ACC MNGR AF

BUILD CODE

DWG NO

PROJECT

AMEND NO



Building Name
ORTIA INTRNTNL

Drawing Description

Construction

INT. ARRIVALS



SPACE PLANNING & BUILDING FACILITIES MANAGEMENT

SCHEDULE: DRYWALLS AND PARTITIONING:				
UNLESS INDICATED OTHERWISE, ALL SARS DRYWALLING IS DW-D4. HEIGHTS INDICATED ARE ASSUMED. ACTUAL HEIGHTS TO BE MEASURED AND INDICATED IN BOQ BY QS. Each 'REF' has a supporting A4 PDF. Contractors to study before pricing any Bils.				
DRY-WALLING REFERENCE CODES:				
REF	DESCRIPTION	SYSTEM TYPICAL HEIGHT WIDTH	LOCATION	CAD LINES
DW-K1	Removal Sound Block STD	120mm 3000 FTL to US Slab	As indicated per plan	██████████
DW-K2	Removal HSSpec 2 Hour Fire Rated	102mm 3000 FTL to US Slab	As indicated per plan	██████████
DW-K3	Removal HSSpec 2 Hour Fire Rated & Steel Reinforced	102mm 3000 FTL to US Slab	Server Room	██████████
DW-K4	Removal 90mm Drywall	90mm 3000 FTL to US ceiling	unless other was stated	██████████
DW-K5	Removal HSSpec 2 Hour Fire Rated	102mm 3000 FTL to US Slab	Patch Room	██████████
DW-K7	Removal 100mm Acoustic Finishsheet	90mm 3000 FTL to US ceiling	Barbican	██████████
DW-K8	Removal Sound Block STD	91mm 3000 FTL to US Slab	Forensic Lab	██████████
DW-K9	Removal Double Glaz Strengthened	120mm 3000 FTL to US ceiling	Support Walls as reqd.	██████████
DW-K10	New Single Brick Wall	115mm 3000 FTL to US ceiling	As indicated per plan	██████████
DW-K11	New Double Brick Wall	220mm 3000 FTL to US ceiling	As indicated per plan	██████████

